

Pressure Spike Standard Operating Procedure

Purpose

This SOP explains the required response when process pressure exceeds 140 PSI.

Immediate Actions

- Notify the control room.
- Verify sensor readings.
- Reduce pump RPM by 20%.
- Check discharge valve position.
- Inspect pressure relief valve.

Possible Causes

- Valve blockage
- Pump cavitation
- Closed downstream valve
- Sensor malfunction

Maintenance

Inspect seals and bearings.

Check pipeline restrictions.

Verify pressure transmitter calibration.

Recovery

Pressure must remain below 135 PSI
for at least five minutes before restarting.